



**agriculture
& rural development**

Department:
agriculture
& rural development
PROVINCE OF KWAZULU-NATAL

**KWAZULU-NATAL DEPARTMENT OF AGRICULTURE AND RURAL
DEVELOPMENT**

Quotation No: R/S/1920/1480

**SUPPLY, DELIVER, OFFLOAD AND ERECT REFABRICATED FOR 21
HOUSEHOLD GARDENS IN DANNHAUSER MUNICIPALITY – AMAJUBA
DISTRICT**

NAME OF BIDDER: _____

COMPULSORY SITE BRIEFING DETAILS	
DATE	04/03/2020
MEETING VENUE	AGRICULTURE LOCAL OFFICE
MEETING ADDRESS	12 CHURCH STREET DANNHAUSER LOCAL OFFICE
MEETING TIME	
START TIME	11:00 AM

1. PRE-QUALIFICATION CRITERIA

REQUIREMENT-CIDB Grading: 1 CE, ME OR GB

Evaluation will be in terms of the 80/20 preference point system

For more information, please contact the following official:

**For: Technical Enquiries:
Mr K.S Hlongwa
076 947 1644 /082 3393 110**

**For: Quotation/SCM enquiries:
Ms Bongie Mbokazi
033-343 8312**

CLOSING DATE: 13 MARCH 2020

TIME: 11:00 AM



agriculture & rural development

Department:
agriculture
& rural development
PROVINCE OF KWAZULU-NATAL

INVITATION OF QUOTATION ABOVE R30,000.00

THIS FORM SHOULD BE COMPLETED IN DETAIL AND SHOULD BE ACCOMPANIED BY A **VALID TAX COMPLIANCE STATUS PIN AND VALID BBBEE VERIFICATION CERTIFICATE/AFFIDAVIT**

QUOTATION NUMBER: R/S/1920/1480	VALIDITY PERIOD OF QUOTATION..... Days (To be completed by the Supplier)
CLOSING DATE: 03/03/2020	CLOSING TIME: 11H00
DESCRIPTION(SPECIFICATION/S) OF ITEMS/ SERVICE REQUIRED: SUPPLY, DELIVER, OFFLOAD AND ERECT REFRATED FOR 21 HOUSEHOLD GARDENS IN DANHAUSER MUNICIPALITY- AMAJUBA DISTRICT SEE ATTACHED SPEC	COMPANY NAME: TEL NO: FAX NO: CONTACT PERSON: CSD REG NUMBER MAAA.....
DOES OFFER COMPLY WITH SPECIFICATION?	YES/NO (DELETE WHICH EVER IS NOT APPLICABLE)
DOES ARTICLE COMPLY WITH SABS SPECIFICATION? HAS IT BEEN INSPECTED BY SABS?	YES/NO YES/NO (DELETE WHICH EVER IS NOT APPLICABLE)
DELIVERY PERIOD AFTER INITIAL ORDER?	
IS THE PRICE FIRM	
WHERE ARE THE STOCK HELD? (PHYSICAL ADDRESS , PLEASE)-	
QUOTATION PRICE INCLUDING VAT (VAT TO BE ADDED BY REGISTERED VAT VENDORS ONLY)	TOTAL: R
COMPANY OFFICIAL STAMP (COMPULSORY) SIGNATURE OF BIDDER DATE
NUMBER OF PAGES FAXED BACK TO THE DEPARTMENT BY THE SUPPLIER(Supplier to complete)

NB: QUOTATIONS MUST BE DEPOSITED IN THE BID BOX SITUATED AT: THE DEPARTMENT OF AGRICULTURE & RURAL DEVELOPMENT:4 PIN OAK AVENUE HILTON

FOR THE ATTENTION OF: BONGI MBOKAZI
TELEPHONE NUMBER: 033- 343 8312

NB: THE ATTACHED SBD4 & SBD9 FORMS MUST BE COMPLETED .THIS QUOTATION COVER PAGE MUST BE COMPLETED AND RETURNED WITH ALL YOUR QUOTATION DOCUMENTS.

1480

COMPANY NAME :
ADDRESS :
CONTACT PERSON :
CONTACT NUMBER :
FAX NUMBER :

LINE NO.	DESCRIPTION OR SPECIFICATION OF ITEM (Please be very specific and clear)	REQUIRED QUANTITY	UNIT PRICE EXCL. VAT		TOTAL PRICE	
			R	C	R	C
	Supply, deliver and offload prefabricated fence 0.84 km for 21 household gardens: see attached specifications	21				
* LABOUR (IF APPLICABLE)						
*DELIVERY (IF APPLICABLE)						
TOTAL						
*ONLY APPLICABLE TO VAT REGISTERED SUPPLIERS 15% VAT						
TOTAL PRICE						

*VAT Registration No. (Supplier) -----

When Required (Requester): 10 December 2019

Where Required (Requester): 12 Church street Dannhauser

Contact details of requester: N.D Mkhize

TEL : 0343 621 3080/076 821 8855

COMPANY STAMP

PRICES ARE VALID FOR

Mark one Box (X)

30	60	90
----	----	----

DAYS

SIGNATURE

DATE

KZN Department of Agriculture and Rural Development



UMNYANGO: EZOLIMO EZEMVELO NOKUTHUKISWA
KWEMIPHAKATHI YASEMAKHAYA - ISIFUNDAZWE SAKWAZULU-NATALI

BID DOCUMENT FOR THE CONSTRUCTION OF: HINGED JOINT FENCE WITH 3 STRANDS BARBED WIRE ON TOP

Project: Danhouser HH garden

TABLE OF CONTENTS:

No.	Section	Pages	Read / Complete
1.	Project Particulars and Specification	1-4	Read
2.	Bill of Quantities	5	Complete
3.	Drawing A1	6	Read
4.	Map of fence layout	7	Read

Appointment of a Service Provider to erect 0.04 kms hinged joint fence at 10m x 10m HH garden

1. Background:

The fence is to be erected approximately 75 km from Newcastle

2. Specific Objective:

Supply, deliver and fully erect a hinged joint fence of 0.04 km.

The fence must be erected in accordance with the specification in the attached drawing, Drawing A1.

3. Scope of Objectives:

Supply and erect a 1.2m hinged joint fence with 3 strands of double twist barbed wire above.

The following services are required:

- 3.1 Supply: - of the specified materials listed in the Bill Of Quantities, Appendix 1.
- 3.2 Delivery: - of all materials to 27km's
- 3.3 Erection:
 - according to the attached map, showing the fence layout.
 - according to the Departmental Specifications in the attached drawing, Drawing A1.
 - providing all equipment required for erection
 - sourcing of at least 50% unskilled labour from the local community.
- 3.4 Inspection and reporting:
 - weekly inspection reports of progress must be submitted on Monday morning to the contact person.
 - On site inspections will be conducted by the Departmental staff to check all completed work before any payments will be made.
 - The contractor is responsible to check that the tendered distance is correct. Failure to check the distance before starting the installation will result in the contractor not being paid for any excess/extra material that the contractor has purchased. The contractor will only be paid for materials that have been used. Where the tendered distances is lower than the required distance the contractor must not exceed the tender amount prior to receiving authorization in the form of a variation order.
 - Accurate distances of all erected fences are to be kept by the service provider as only work that has been done will be paid for. Any fencing installed over the order amount will not be paid for unless prior permission has been obtained to exceed the order amount.
 - Site meetings and project steering committee meetings to be held when necessary and minutes to be kept by the service provider.

4. Deliverables:

- 4.1 Fencing materials according to the Bill of Quantities in Appendix 1.
- 4.2 Construction of the fence according to the specifications provided in Drawing A1.
If Drawing A1 was not attached to the tender documents it is the contractors responsibility to obtain the drawing before submitting the tender. Failure to erect the fence according to the Departmental specification will result in the contractor having to re-install the fence at the contractors own expense.
- 4.3 Weekly written progress reports to the Local Agricultural Manager, outlining progress, daily activities and quantities of materials used.
- 4.4 Submission of full closeout report including materials used, job opportunities created in EPWP format for the duration of the project.
- 4.5 Attendance of steering committee meetings and the provision of minutes if called for.
- 4.6 The contract requires a minimum delivery of 3 km of completed fencing per week.

5. Competence and Expertise:

It is essential that the work be carried out by fully competent personnel with proven experience in fencing and Project Management.

- 5.1 Competency:
 - only bidders with proven ability to complete 3 km per week shall be considered.
 - bidders are required to provide an implementation plan including time frames from start to finish.
 - failure to provide a program will invalidate the bid.
- 5.2 Labour:
 - skilled and semi-skilled labour only to be provided by the contractor. At least 50%

unskilled labour is to be sourced from the local community.

5.3 Site supervision -Project Manager/Technician on site to supervise work done, quality control and certify work for payment. Estimated time for payment is 6 weeks.

5.4 Bid Format: All documents in the bid document are to be completed. All quotations and claims must include VAT.

6. Validity Period for Bid:

Bids shall remain valid for a period of 90 days from the date that the bid closes.

7. Compulsory Pre-Bid Tender Meeting:

A compulsory pre-bid site meeting will be held with prospective bidders. Failure to attend this meeting will invalidate the bid.

8. Site Hand Over to the Contractor:

The contractor will be introduced to the project participants following the awarding of the tender. The site will be handed over to the contractor who will control the site for the duration of the project. The contractor will be responsible for the administration, control and security for the site. It is up to the contractor to arrange insurance as the contractor is responsible for and theft or damage that occurs on site and will have to pay for any repairs or replacements.

9. Water and Electricity:

There is no piped water and electricity on site. The contractor shall make the necessary arrangements for the provision of any water and electricity. Any cost to acquire water and electricity must be added to the bid amount as no extra funding will be received.

10. Housing of Contractors Employees:

No housing is available for the contractors employees and the contractor shall make arrangements to house any labour and transport them to and from site. It is up to the contractor to arrange any short term accommodation with the project participants. The contractor is responsible for any financial expenses for housing employees on site.

11. Underground Cables and Pipes:

If such services are discovered, immediate notification must be made to the Employer and all work in the vicinity will cease until it is safe to continue. If the contractor damages any underground pipes or cables such damage will be repaired as soon as it is safe and possible by the contractor, at his own expense.

12 Insurance

All accepted approved contractors shall be required to provide the following insurance's for the project awarded to them:

- i) Registration with the Compensation Commissioner and compliance with the Compensation for Occupational Injuries and Diseases Act with regard to insurance.
- ii) Unemployment fund insurance for all workers.
- iii) Insurance against damage, destruction or loss caused by fire.
- iv) Public Liability insurance.
- v) All Risks (works) Policy Political for the value of the respective project plus 10%.

13. Specification:

Refer to Bill of Quantities and Drawings .

- Spacing:
10% maximum variation from the specified spacing will be accepted.
- Boxes:
Minimum length to be 1.2m.
- Compaction:
Normal manual force against the poles must be absorbed.
- Straining:
The hinged joint section and barbed wire to be strained.
If the fence is pulled down, it must recover to it's original position. Fence is to be strained using

appropriate straining equipment.

- Exposed Surfaces:

All exposed surfaces where poles have been sawed off are to be painted with creosote.

14. Timetable/Timing:

The contractor must be on site and commence construction no later than 1 week after an order has been issued. Where more than 1 payment is required, the contractor must indicate the number of part payments that will be required in the tender documents. Claims for work that has been completed and verified can be submitted on a monthly basis. No more than 1 claim per month will be accepted.

15. Management Arrangements and Reporting Requirements:

0 is the District Manager. Any matters regarding the district staff or any complaints should be directed to him/her.

16. Evaluation Criteria:

Proven previous experience is a requirement to qualify.

Award of work to the successful bidder will be based on Price, Departmental Goals (i.e. preference points as per ZNT 30 attached) and functionality.

16.1 Compliance:

- i) All information and documentation required in the Specification, eg. Certificates.
- ii) All information required in the bid document must be accurate and duly completed, including all the appropriate signatures. This includes the submission of required / requested documentation eg. valid tax certificate, ZNT 30 etc.
- iii) Failure to comply with any of the requirements will invalidate the bid.

16.2 The 80/20 Preference Points System:

Bids that are less than R500 000 will apply the 80/20 preference points system, where 80 points will be used for pricing scores only and 20 points for HDI status. Bids greater than R500 000 will apply the 90/10 system.

i) GOALS	GOALS 80/20	GOALS	GOALS 90/10
No Franchise	10 points	No Franchise	5 Points
Women	6 points	Women	3 Points
Youth	4 points	Youth	2 Points

ii) Functionality:

Criteria	Guidelines for evaluation criteria applications
Ability	Bidders to provide proof of current capacity and ability to manage and implement a project of this magnitude.
Capacity	
Capability	Demonstration of capability and competency to render the required service.
Competency	Bidders to provide evidence of similar projects completed.
Experience	
Methodology	Provide a short description of your intended implementation methodology, indicating time frames to complete the work.

Evaluation Criteria for Functionality:

Note: in order to ensure meaningful evaluation, bidders must submit detailed information in substantiation of the evaluation criteria mentioned. Failure to provide supporting information requested above will invalidate the bid.

16.3 General:

The Department of Agriculture, Environmental Affairs and Rural Development is an equal opportunity, affirmative action employer. It shows the same commitment to those who wish to provide services to the Department via the procurement process. This does not preclude the formation of consortiums or the inclusion of proposals on how this project can be used to further the aims of transformation.

The actual price quoted, including VAT, will be used for issuing of an order to the successful bidder. You must provide for all items in Appendix 1 as the unit rates quoted will be applied for calculation of the amount claimable.

17. Payment Schedule:

Claims for work that has been completed can be made according to the following payment schedule:

1	Site Establishment:	5%
2	Material delivered to site (with invoice)	Invoiced Amount
3	Completed sections of fence (per m)	pro rata tender amount (less 1+2+4)
4	Retention	5%

A 5% retention will be kept for 3 months after works have been completed to make sure that the standard of work that has been done is satisfactory.

18. Enquiries:

Mr MJ Nhleko District Director 034-3124614

W. Mabaso Project manager 034-3124614

APPENDIX 1: BILL OF QUANTITIES

1.2m Hinged joint fence with 3 strands of barbed wire above (Total Height 1.7m)

Project: Dannhouser HH garden

Fence Perimeter = 40 m

District Amajuba

Bonnox fence for irrigation area only

Contact Person Winston

Contact Number 823 303 663

No.	Item Description	Quantity Required	Unit Price	Total Cost
General:				
1	Site establishment	sum		
2	Site Clearing: Removal of any existing fences. Bush clearing required.	sum		
Materials:				
3	Fully Galvanized barbed wire 1.6mm diameter High Tensile Double Strand - 845m per roll Galvanized Class 0	1 Roll(s)		
4	2.4m Standard Creosote Poles Pressure treated, SABS approved 100 - 125mmØ	28 Poles		
5	Hinged Joint Fence, 1.2m high (eg. Veldspan/Bonnox/or equivalent) Galvanized Class 0 150mm squares, 100m rolls	1 Roll(s)		
6	Galvanized Wire Staples 3.15 x 32mm 500g packs	1 Pack(s)		
7	1.2m x 0.9m pedestrian gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	1 Gate(s)		
8	3.6m x 1.2m Vehicle farm gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	0 Gate(s)		
9	8 ga tie wire, 4mm diam, 5kg roll Galvanized Class 0	2 Roll(s)		
10	2500 litre JoJo tank to be on concrete slab with anchors including a 4m steel gutter feeding JoJo with gutter anchors	1 Roll(s)		
11	Erection Cost	sum		
12	Transport Cost	sum		
SUB-TOTAL				
VAT				
TOTAL				

NOTE: This Bill of Quantities must be read in conjunction with DRAWING no. A1 Dated 22/10/2010

DRAWING REFERENCE

No. 02/16

1/16

NOTES

No.	Description	Date	By
REVISIONS			

Client Approval:

Prepared: B BUS
 Drawn: B WHITTAL
 Designed: B WHITTAL
 Checked: B WHITTAL
 Scale: NTS

DEPARTMENT OF AGRICULTURE,
 ENVIRONMENTAL AFFAIRS AND
 RURAL DEVELOPMENT


PROJECT

SERVICE
 Technical Support Services

DRAWING TITLE



**DRAWING A1
 HINGED JOINT
 FENCE DETAIL**

Drawing No. **131671/GEN2**
 Date: **22/10/2010**
 No. 1/16



NOTE: CORNER BOX IS SIMILAR TO STRAINING BOX

Boxes for Pedestrian and Motor Vehicle Gate are the same as Straining Boxes Gate hinged on Pole



STRAINING BOX DETAIL

NOTES:

1. Poles Creosoted (2.4m x 100-150 mm).
2. Hinged Joint Fence should be approximately 150mm square galv.
3. The hinged joint fence is to be strained by using a special clamp-bar and two wire strainers.
4. The fence is also to be secured onto the hardwood posts and standards by means of staples. The staples are to be installed over the horizontal wires and it is important not to install the staples upright, but at a 45 degree angle.
5. Hinged joint fence shall be installed with the smaller spacings at the bottom.
6. Galvanized barbed wired, double strand above hinged joint fence. One strand to be placed 200mm above hinged joint fence. The other 2 strands 150mm apart.
7. Poles to be placed in holes 700mm deep and very well compacted with soil in layers.
8. Poles are 5m apart.
9. Braces or "Boxes" are 1.2m wide using a pole cut in half for top.
10. Boxes braced with diagonal double 8 ga wire strands twisted to tension.
11. Holes drilled through poles as shown for ties.
12. One box each side of gate. Double box at corners. Box every 100m on long lengths.
13. Pedestrian gate - 900 X 1200 mm
14. Motor vehicle gate - 3.6 X 1.2 m

APPENDIX 1: BILL OF QUANTITIES

1.2m Hinged joint fence with 3 strands of barbed wire above (Total Height 1.7m)

Project: Dannhouser HH garden

Fence Perimeter = 40m

District: Amajuba

Bonnox fence for irrigation area only

Contact Person: Winston

Contact Number: 823 303 663

No.	Item Description	Quantity Required	Unit Price	Total Cost
	General:			
1	Site establishment	sum	nil	
2	Site Clearing: Removal of any existing fences. Bush clearing required.	sum		
	Materials:			
3	Fully Galvanized barbed wire 1.6mm diameter High Tensile Double Strand - 845m per roll Galvanized Class 0	1 Roll(s)		
4	2.4m Standard Creosote Poles Pressure treated, SABS approved 100 - 125mmØ	18 Poles		
5	Hinged Joint Fence, 1.2m high (e.g. Veldspan/Bonnox/or equivalent) Galvanized Class 0 150mm squares, 100m rolls	1 Roll(s)		
6	Galvanized Wire Staples 3.15 x 32mm 500g packs	2 Pack(s)		
7	1.2m x 0.9m pedestrian gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	1 Gate(s)		
8	3.6m x 1.2m Vehicle farm gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	0 Gate(s)		
9	8ga tie wire, 4mm diam, 50kg roll Galvanized Class 0	1 Roll(s)		
10	2500liter JoJo to be on 1m readymade steel stand anchored including coroma gutter attached to roof & feeding JoJo tank	sum		
11	Supply & deliver only	sum		
	SUB-TOTAL			
	VAT			
	TOTAL			

Note: This Bill of Quantities must be in line with the Standard Departmental Bonnox fencing

APPENDIX 1: BILL OF QUANTITIES

1.2m Hinged joint fence with 3 strands of barbed wire above (Total Height 1.7m)

Project: Dannhouser HH garden = (21 HH gardens)

Fence Perimeter = 40m

District: Amajuba

Bonnox fence for irrigation area only

Contact Person: Winston

Contact Number: 823 303 663

No.	Item Description	Quantity Required	Unit Price	Total Cost
General:				
1	Site establishment	sum	nil	
2	Site Clearing: Removal of any existing fences. Bush clearing required.	21	400.00	R8 400.00
Materials:				
3	Fully Galvanized barbed wire 1.6mm diameter High Tensile Double Strand - 845m per roll Galvanized Class 0	21 Roll(s)	708.75	R14 883.75
4	2.4m Standard Creosote Poles Pressure treated, SABS approved 100 - 125mmØ	378 Poles	122.32	R46 236.96
5	Hinged Joint Fence, 1.2m high (e.g. Veldspan/Bonnox/or equivalent) Galvanized Class 0 150mm squares, 100m rolls	21 Roll(s)	2239.55	R47 030.55
6	Galvanized Wire Staples 3.15 x 32mm 500g packs	42 Pack(s)	162.75	R6 835.50
7	1.2m x 0.9m pedestrian gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	21 Gate(s)	563.74	R11 838.54
8	3.6m x 1.2m Vehicle farm gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	0 Gate(s)	1067.74	R0.00
9	8ga tie wire, 4mm diam, 50kg roll Galvanized Class 0	21 Roll(s)	761.23	R15 985.83
10	Supply & deliver only	sum		(balance left) -R13 211.13
11	Transport Cost	sum	1000.00	R15 000.00
SUB-TOTAL				(material only) R166 211.13
VAT (all inclusive)				R0.00
TOTAL (allocated)				R153 000.00

Note: This Bill of Quantities must be in line with the Standard Departmental Bonnox fencing
NB: This quotation is for twenty one house hold gardens combined

DRAWING REFERENCE
 No. 13/6/H/GEN2
 Title

NOTES


No.	Description	Date	By
REVISIONS			

Client Approval: _____
 Date: _____
 Signature: _____
 Position: _____
 Date: _____
 Signature: _____
 Position: _____
 Date: _____
 Signature: _____
 Position: _____



DEPARTMENT OF AGRICULTURE,
 ENVIRONMENTAL AFFAIRS AND
 RURAL DEVELOPMENT

PROJECT: _____
 SERVICE: Technical Support Services
 DRAWING TITLE: DRAWING A1
 HINGED JOINT
 FENCE DETAIL

13/6/H/GEN2
 Drawing No. 22/10/2010
 Date



NOTE: CORNER BOX IS SIMILAR TO STRAINING BOX



STRAINING BOX DETAIL

- NOTES:**
1. Poles Creosoted (2,4m x 100-150 mm).
 2. Hinged Joint Fence should be approximately 150mm square galv.
 3. The hinged joint fence is to be strained by using a special clamp-bar and two wire strainers.
 4. The fence is also to be secured onto the hardwood posts and standards by means of staples. The staples are to be installed over the horizontal wires and it is important not to install the staples upright, but at a 45 degree angle.
 5. Hinged joint fence shall be installed with the smaller spacings at the bottom.
 6. Galvanized barbed wired, double strand above hinged joint fence. One strand to be placed 200mm above hinged joint fence. The other 2 strands 150mm apart.
 7. Poles to be placed in holes 700mm deep and very well compacted with soil in layers.
 8. Poles are 5m apart.
 9. Braces or "Boxes" are 1.2m wide using a pole cut in half for top.
 10. Boxes braced with diagonal double 8 ga wire strands twisted to tension.
 11. Holes drilled through poles as shown for ties.
 12. One box each side of gate. Double box at corners. Box every 100m on long lengths.
 13. Pedestrian gate - 900 X 1200 mm
 14. Motor vehicle gate - 3.6 X 1.2 m

APPENDIX 1: BILL OF QUANTITIES

1.2m Hinged joint fence with 3 strands of barbed wire above (Total Height 1.7m)

Project: Dannhouser HH garden = (21 HH gardens)

Fence Perimeter = 40m

District: Amajuba

Bonnox fence for irrigation area only


Contact Person: Winston

Contact Number: 823 303 663


No.	Item Description	Quantity Required	Unit Price	Total Cost
General:				
1	Site establishment	sum	nil	
2	Site Clearing: Removal of any existing fences. Bush clearing required.	21		
Materials:				
3	Fully Galvanized barbed wire 1.6mm diameter High Tensile Double Strand - 845m per roll Galvanized Class 0	21 Roll(s)		
4	2.4m Standard Creosote Poles Pressure treated, SABS approved 100 - 125mmØ	378 Poles		
5	Hinged Joint Fence, 1.2m high (e.g. Veldspan/Bonnox/or equivalent) Galvanized Class 0 150mm squares, 100m rolls	21 Roll(s)		
6	Galvanized Wire Staples 3.15 x 32mm 500g packs	42 Pack(s)		
7	1.2m x 0.9m pedestrian gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	21 Gate(s)		
8	3.6m x 1.2m Vehicle farm gate Hot dip galvanized finish 40 - 50mm diam pipe frame wall thickness of 1.6mm min Hinge eye bolts, include chain	0 Gate(s)		
9	8ga tie wire, 4mm diam, 50kg roll Galvanized Class 0	21 Roll(s)		
10	Supply & deliver only	sum		
SUB-TOTAL				
VAT				
TOTAL				

Note: This Bill of Quantities must be in line with the Standard Departmental Bonnox fencing

NB: This quotation is for twenty one house hold gardens combined



NOTE: CORNER BOX IS SIMILAR TO STRAINING BOX



NOTES:

1. Poles Creosoted (2,4m x 100-150 mm).
2. Hinged Joint Fence should be approximately 150mm square gap.
3. The hinged joint fence is to be strained by using a special clamp-bar and two wire strainers.
4. The fence is also to be secured onto the hardwood posts and standards by means of staples. The staples are to be installed over the horizontal wires and it is important not to install the staples upright, but at a 45 degree angle.
5. Hinged joint fence shall be installed with the smaller spacings at the bottom.
6. Galvanized barbed wired, double strand above hinged joint fence. One strand to be placed 200mm above hinged joint fence. The other 2 strands 150mm apart.
7. Poles to be placed in holes 700mm deep and very well compacted with soil in layers.
8. Poles are 5m apart.
9. Braces or "Boxes" are 1,2m wide using a pole cut in half for top.
10. Boxes braced with diagonal double 8 ga wire strands twisted to tension.
11. Holes drilled through poles as shown for ties.
12. One box each side of gate. Double box at corners. Box every 100m on long lengths.
13. Pedestrian gate - 900 X 1200 mm
14. Motor vehicle gate - 3.6 X 1.2 m

DRAWING REFERENCE	
No	Title

NOTES

No	Description	Date	By

Client Approval: _____
 Endorsement: _____
 Drawn: B BUS
 Designed: B WIRTHL
 Checked: B WIRTHL
 Scale: NTS

DEPARTMENT OF AGRICULTURE,
 ENVIRONMENTAL AFFAIRS AND
 RURAL DEVELOPMENT

PROJECT: _____
 SERVICE: Technical Support Services
 DRAWING TITLE: DRAWING A1 HINGED JOINT FENCE DETAIL
 Drawing No: 13/6/11/GEN2 Date: 22/10/2010

DECLARATION OF INTEREST

1. Any legal person, including persons employed by the state¹, or persons having a kinship with persons employed by the state, including a blood relationship, may make an offer or offers in terms of this invitation to bid (includes an advertised competitive bid, a limited bid, a proposal or written price quotation). In view of possible allegations of favouritism, should the resulting bid, or part thereof, be awarded to persons employed by the state, or to persons connected with or related to them, it is required that the bidder or his/her authorised representative declare his/her position in relation to the evaluating/adjudicating authority where-
 - the bidder is employed by the state; and/or
 - the legal person on whose behalf the bidding document is signed, has a relationship with persons/a person who are/is involved in the evaluation and or adjudication of the bid(s), or where it is known that such a relationship exists between the person or persons for or on whose behalf the declarant acts and persons who are involved with the evaluation and or adjudication of the bid.

 2. **In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.**
 - 2.1 Full Name of bidder or his or her representative:
.....
 - 2.2 Identity Number:
.....
 - 2.3 Position occupied in the Company (director, trustee, shareholder², member):
.....
 - 2.4 Registration number of company, enterprise, close corporation, partnership agreement or trust:
.....
 - 2.5 Tax Reference Number:
.....
 - 2.6 VAT Registration Number:
.....
 - 2.6.1 The names of all directors / trustees / shareholders / members, their individual identity numbers, tax reference numbers and, if applicable, employee / PERSAL numbers must be indicated in paragraph 3 below.
-

1"State" means –

- (a) any national or provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act No. 1 of 1999);
- (b) any municipality or municipal entity;
- (c) provincial legislature;
- (d) national Assembly or the national Council of provinces; or
- (e) Parliament.

2"Shareholder" means a person who owns shares in the company and is actively involved in the management of the enterprise or business and exercises control over the enterprise.

Please clearly indicate, with an 'X' only one box that is applicable to your business or firm

2.7 Are you or any person connected with the bidder presently employed by the state?

YES	NO
-----	----

2.7.1 If so, furnish the following particulars:

Name of person / director / trustee / shareholder/member:

.....

Name of state institution at which you or the person connected to the bidder is employed

.....

Position occupied in the state institution:

.....

Any other particulars:

.....

2.7.2 If you are presently employed by the state, did you obtain

YES	NO
-----	----

the appropriate authority to undertake remunerative work outside employment in the public sector?

If yes, did you attach proof of such authority to the bid document?

YES	NO
-----	----

(Note: Failure to submit proof of such authority, where applicable, may result in the disqualification of the bid.)

2.7.2.1 If no, furnish reasons for non-submission of such proof:

.....

.....

2.8 Did you or your spouse, or any of the company's directors / trustees / shareholders / members or their spouses conduct business with the state in the previous twelve months?

YES	NO
-----	----

2.8.1 If so, furnish particulars:

.....
.....

2.9 Do you, or any person connected with the bidder, have any relationship (family, friend, other) with a person employed by the state and who may be involved with the evaluation and or adjudication of this bid?

YES	NO
-----	----

2.9.1 If so, furnish particulars.

.....
.....

2.10 Are you, or any person connected with the bidder, aware of any relationship (family, friend, other) between any other bidder and any person employed by the state who may be involved with the evaluation and or adjudication of this bid?

YES	NO
-----	----

2.10.1 If so, furnish particulars.

.....
.....

2.11 Do you or any of the directors / trustees / shareholders / members of the company have any interest in any other related companies whether or not they are bidding for this contract?

YES	NO
-----	----

2.11.1 If so, furnish particulars:

.....
.....

3 Full details of directors / trustees / members / shareholders.

Full Name	Identity Number	Personal Income Tax Reference Number	State Employee Number / Persal Number

4 DECLARATION

I, THE UNDERSIGNED (NAME).....

CERTIFY THAT THE INFORMATION FURNISHED IN PARAGRAPHS 2 and 3 ABOVE IS CORRECT.

I ACCEPT THAT THE STATE MAY REJECT THE BID OR ACT AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

.....
Name of bidder

.....
Position

.....
Signature

.....
Date

CERTIFICATE OF INDEPENDENT BID DETERMINATION

- 1 This Standard Bidding Document (SBD) must form part of all bids¹ invited.
- 2 Section 4 (1) (b) (iii) of the Competition Act No. 89 of 1998, as amended, prohibits an agreement between, or concerted practice by, firms, or a decision by an association of firms, if it is between parties in a horizontal relationship and if it involves collusive bidding (or bid rigging).² Collusive bidding is a *per se* prohibition meaning that it cannot be justified under any grounds.
- 3 Treasury Regulation 16A9 prescribes that accounting officers and accounting authorities must take all reasonable steps to prevent abuse of the supply chain management system and authorizes accounting officers and accounting authorities to:
 - a. disregard the bid of any bidder if that bidder, or any of its directors have abused the institution's supply chain management system and or committed fraud or any other improper conduct in relation to such system.
 - b. cancel a contract awarded to a supplier of goods and services if the supplier committed any corrupt or fraudulent act during the bidding process or the execution of that contract.
- 4 This SBD serves as a certificate of declaration that would be used by institutions to ensure that, when bids are considered, reasonable steps are taken to prevent any form of bid-rigging.
- 5 In order to give effect to the above, the attached Certificate of Bid Determination (SBD 9) must be completed and submitted with the bid:

¹ Includes price quotations, advertised competitive bids, limited bids and proposals.

² Bid rigging (or collusive bidding) occurs when businesses, that would otherwise be expected to compete, secretly conspire to raise prices or lower the quality of goods and / or services for purchasers who wish to acquire goods and / or services through a bidding process. Bid rigging is, therefore, an agreement between competitors not to compete.

CERTIFICATE OF INDEPENDENT BID DETERMINATION

I, the undersigned, in submitting the accompanying bid:

_____ (Bid Number and Description)

in response to the invitation for the bid made by:

_____ (Name of Institution)

do hereby make the following statements that I certify to be true and complete in every respect:

I certify, on behalf of _____ that:
(Name of Bidder)

1. I have read and I understand the contents of this Certificate;
2. I understand that the accompanying bid will be disqualified if this Certificate is found not to be true and complete in every respect;
3. I am authorized by the bidder to sign this Certificate, and to submit the accompanying bid, on behalf of the bidder;
4. Each person whose signature appears on the accompanying bid has been authorized by the bidder to determine the terms of, and to sign the bid, on behalf of the bidder;
5. For the purposes of this Certificate and the accompanying bid, I understand that the word "competitor" shall include any individual or organization, other than the bidder, whether or not affiliated with the bidder, who:
 - (a) has been requested to submit a bid in response to this bid invitation;
 - (b) could potentially submit a bid in response to this bid invitation, based on their qualifications, abilities or experience; and
 - (c) provides the same goods and services as the bidder and/or is in the same line of business as the bidder
6. The bidder has arrived at the accompanying bid independently from, and without consultation, communication, agreement or arrangement with any competitor. However communication between partners in a joint venture or consortium³ will not be construed as collusive bidding.

7. In particular, without limiting the generality of paragraphs 6 above, there has been no consultation, communication, agreement or arrangement with any competitor regarding:
 - (a) prices;
 - (b) geographical area where product or service will be rendered (market allocation)
 - (c) methods, factors or formulas used to calculate prices;
 - (d) the intention or decision to submit or not to submit, a bid;
 - (e) the submission of a bid which does not meet the specifications and conditions of the bid; or
 - (f) bidding with the intention not to win the bid.
8. In addition, there have been no consultations, communications, agreements or arrangements with any competitor regarding the quality, quantity, specifications and conditions or delivery particulars of the products or services to which this bid invitation relates.
9. The terms of the accompanying bid have not been, and will not be, disclosed by the bidder, directly or indirectly, to any competitor, prior to the date and time of the official bid opening or of the awarding of the contract.
10. I am aware that, in addition and without prejudice to any other remedy provided to combat any restrictive practices related to bids and contracts, bids that are suspicious will be reported to the Competition Commission for investigation and possible imposition of administrative penalties in terms of section 59 of the Competition Act No 89 of 1998 and or may be reported to the National Prosecuting Authority (NPA) for criminal investigation and or may be restricted from conducting business with the public sector for a period not exceeding ten (10) years in terms of the Prevention and Combating of Corrupt Activities Act No 12 of 2004 or any other applicable legislation.

.....
Signature

.....
Date

.....
Position

.....
Name of Bidder

OFFICIAL BRIEFING SESSION/SITE INSPECTION CERTIFICATE

N. B.: THIS FORM IS ONLY TO BE INCLUDED AND COMPLETED WHEN APPLICABLE TO THE BID.

Site/building/institution involved:
.....

Bid No:

Service:

THIS IS TO CERTIFY THAT (NAME):

ON BEHALF OF:

VISITED AND INSPECTED THE SITE ON..... (DATE)

AND IS THEREFORE FAMILIAR WITH THE CIRCUMSTANCES AND THE SCOPE OF THE SERVICE TO BE RENDERED.

.....
SIGNATURE OF BIDDER OR AUTHORISED REPRESENTATIVE
(PRINT NAME)

DATE:

.....
SIGNATURE OF DEPARTMENTAL REPRESENTATIVE
(PRINT NAME)

.....
DEPARTMENTAL STAMP:
(OPTIONAL)

DATE:

Local Content

SBD 6.2

DECLARATION CERTIFICATE FOR LOCAL PRODUCTION AND CONTENT FOR DESIGNATED SECTORS

This Standard Bidding Document (SBD) must form part of all bids invited. It contains general information and serves as a declaration form for local content (local production and local content are used interchangeably).

Before completing this declaration, bidders must study the General Conditions, Definitions, Directives applicable in respect of Local Content as prescribed in the Preferential Procurement Regulations, 2011, the South African Bureau of Standards (SABS) approved technical specification number SATS 1286:2011 (Edition 1) and the Guidance on the Calculation of Local Content together with the Local Content Declaration Templates [Annex C (Local Content Declaration: Summary Schedule), D (Imported Content Declaration: Supporting Schedule to Annex C) and E (Local Content Declaration: Supporting Schedule to Annex C)].

1. General Conditions

- 1.1. Preferential Procurement Regulations, 2011 (Regulation 9) makes provision for the promotion of local production and content.
- 1.2. Regulation 9.(1) prescribes that in the case of designated sectors, where in the award of bids local production and content is of critical importance, such bids must be advertised with the specific bidding condition that only locally produced goods, services or works or locally manufactured goods, with a stipulated minimum threshold for local production and content will be considered.
- 1.3. Where necessary, for bids referred to in paragraph 1.2 above, a two stage bidding process may be followed, where the first stage involves a minimum threshold for local production and content and the second stage price and B-BBEE.
- 1.4. A person awarded a contract in relation to a designated sector, may not sub-contract in such a manner that the local production and content of the overall value of the contract is reduced to below the stipulated minimum threshold.
- 1.5. The local content (LC) expressed as a percentage of the bid price must be calculated in accordance with the SABS approved technical specification number SATS 1286: 2011 as follows:

$$LC = [1 - x / y] * 100$$

Where

x is the imported content in Rand

y is the bid price in Rand excluding value added tax (VAT)

Prices referred to in the determination of x must be converted to Rand (ZAR) by using the exchange rate published by South African Reserve Bank (SARB) at 12:00 on the date of advertisement of the bid as indicated in paragraph 4.1 below.

The SABS approved technical specification number SATS 1286:2011 is accessible on [http://www.thedti.gov.za/industrial development/ip.jsp](http://www.thedti.gov.za/industrial%20development/ip.jsp) at no cost.

1.6 A bid may be disqualified if –

- (a) this Declaration Certificate and the Annex C (Local Content Declaration: Summary Schedule) are not submitted as part of the bid documentation; and
- (b) the bidder fails to declare that the Local Content Declaration Templates (Annex C, D and E) have been audited and certified as correct.

2. Definitions

- 2.1. **“bid”** includes written price quotations, advertised competitive bids or proposals;
 - 2.2. **“bid price”** price offered by the bidder, excluding value added tax (VAT);
 - 2.3. **“contract”** means the agreement that results from the acceptance of a bid by an organ of state;
 - 2.4. **“designated sector”** means a sector, sub-sector or industry that has been designated by the Department of Trade and Industry in line with national development and industrial policies for local production, where only locally produced services, works or goods or locally manufactured goods meet the stipulated minimum threshold for local production and content;
 - 2.5. **“duly sign”** means a Declaration Certificate for Local Content that has been signed by the Chief Financial Officer or other legally responsible person nominated in writing by the Chief Executive, or senior member / person with management responsibility (close corporation, partnership or individual).
 - 2.6. **“imported content”** means that portion of the bid price represented by the cost of components, parts or materials which have been or are still to be imported (whether by the supplier or its subcontractors) and which costs are inclusive of the costs abroad (this includes labour or intellectual property costs), plus freight and other direct importation costs, such as landing costs, dock duties, import duty, sales duty or other similar tax or duty at the South African port of entry;
 - 2.7. **“local content”** means that portion of the bid price which is not included in the imported content, provided that local manufacture does take place;
 - 2.8. **“stipulated minimum threshold”** means that portion of local production and content as determined by the Department of Trade and Industry; and
 - 2.9. **“sub-contract”** means the primary contractor’s assigning, leasing, making out work to, or employing another person to support such primary contractor in the execution of part of a project in terms of the contract.
3. **The stipulated minimum threshold(s) for local production and content (refer to Annex A of SATS 1286:2011) for this bid is/are as follows:**

<u>Description of services, works or goods</u>	<u>Stipulated minimum threshold</u>
<u>Steel product</u>	<u>100</u> %
_____	_____ %
_____	_____ %

4. Does any portion of the services, works or goods offered have any imported content?
(Tick applicable box)

YES	<input type="checkbox"/>	NO	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

- 4.1 If yes, the rate(s) of exchange to be used in this bid to calculate the local content as prescribed in paragraph 1.5 of the general conditions must be the rate(s) published by SARB for the specific currency at 12:00 on the date of advertisement of the bid.

The relevant rates of exchange information is accessible on www.reservebank.co.za.

Indicate the rate(s) of exchange against the appropriate currency in the table below (refer to Annex A of SATS 1286:2011):

Currency	Rates of exchange
US Dollar	
Pound Sterling	
Euro	
Yen	
Other	

NB: Bidders must submit proof of the SARB rate (s) of exchange used.

5. Were the Local Content Declaration Templates (Annex C, D and E) audited and certified as correct?
(Tick applicable box)

YES	<input type="checkbox"/>	NO	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

- 5.1. If yes, provide the following particulars:

- (a) Full name of auditor:
- (b) Practice number:
- (c) Telephone and cell number:
- (d) Email address:

(Documentary proof regarding the declaration will, when required, be submitted to the satisfaction of the Accounting Officer / Accounting Authority)

6. Where, after the award of a bid, challenges are experienced in meeting the stipulated minimum threshold for local content the dti must be informed accordingly in order for the dti to verify and in consultation with the AO/AA provide directives in this regard.

LOCAL CONTENT DECLARATION
(REFER TO ANNEX B OF SATS 1286:2011)

LOCAL CONTENT DECLARATION BY CHIEF FINANCIAL OFFICER OR OTHER LEGALLY RESPONSIBLE PERSON NOMINATED IN WRITING BY THE CHIEF EXECUTIVE OR SENIOR MEMBER/PERSON WITH MANAGEMENT RESPONSIBILITY (CLOSE CORPORATION, PARTNERSHIP OR INDIVIDUAL)

IN RESPECT OF BID NO.

ISSUED BY: (Procurement Authority / Name of Institution):

NB

1 The obligation to complete, duly sign and submit this declaration cannot be transferred to an external authorized representative, auditor or any other third party acting on behalf of the bidder.

2 Guidance on the Calculation of Local Content together with Local Content Declaration Templates (Annex C, D and E) is accessible on http://www.thdti.gov.za/industrial_development/ip.jsp. Bidders should first complete Declaration D. After completing Declaration D, bidders should complete Declaration E and then consolidate the information on Declaration C. **Declaration C should be submitted with the bid documentation at the closing date and time of the bid in order to substantiate the declaration made in paragraph (c) below.** Declarations D and E should be kept by the bidders for verification purposes for a period of at least 5 years. The successful bidder is required to continuously update Declarations C, D and E with the actual values for the duration of the contract.

I, the undersigned, (full names),
 do hereby declare, in my capacity as
 of(name of bidder
 entity), the following:

(a) The facts contained herein are within my own personal knowledge.

(b) I have satisfied myself that:

- (i) the goods/services/works to be delivered in terms of the above-specified bid comply with the minimum local content requirements as specified in the bid, and as measured in terms of SATS 1286:2011; and
- (ii) the declaration templates have been audited and certified to be correct.

(c) The local content percentage (%) indicated below has been calculated using the formula given in clause 3 of SATS 1286:2011, the rates of exchange indicated in paragraph 4.1 above and the information contained in Declaration D and E which has been consolidated in Declaration C:

Bid price, excluding VAT (y)	R
Imported content (x), as calculated in terms of SATS 1286:2011	R
Stipulated minimum threshold for local content (paragraph 3 above)	
Local content %, as calculated in terms of SATS 1286:2011	

If the bid is for more than one product, the local content percentages for each product contained in Declaration C shall be used instead of the table above.

The local content percentages for each product has been calculated using the formula given in clause 3 of SATS 1286:2011, the rates of exchange indicated in paragraph 4.1 above and the information contained in Declaration D and E.

(d) I accept that the Procurement Authority / Institution has the right to request that the local content be verified in terms of the requirements of SATS 1286:2011.

(e) I understand that the awarding of the bid is dependent on the accuracy of the information furnished in this application. I also understand that the submission of incorrect data, or data that are not verifiable as described in SATS 1286:2011, may result in the Procurement Authority / Institution imposing any or all of the remedies as provided for in Regulation 13 of the Preferential Procurement Regulations, 2011 promulgated under the Preferential Policy Framework Act (PPFA), 2000 (Act No. 5 of 2000).

SIGNATURE: _____

DATE: _____

WITNESS No. 1 _____

DATE: _____

WITNESS No. 2 _____

DATE: _____

Annex C

Local Content Declaration - Summary Schedule

(C1) Tender No.			
(C2) Tender description:			
(C3) Designated product(s)			
(C4) Tender Authority:			
(C5) Tendering Entity name:			
(C6) Tender Exchange Rate:	Pula	EU	GBP
(C7) Specified local content %			

Note: VAT to be excluded from all calculations

Tender item no's	List of items	Calculation of local content				Local content % (per item)	
		Tender price - each (excl VAT)	Exempted Imported value	Tender value net of exempted Imported content	Imported value		
(C8)	(C9)	(C10)	(C11)	(C12)	(C13)	(C14)	(C15)

Tender summary			
Tender Qty	Total tender value	Total exempted Imported content	Total Imported content
(C16)	(C17)	(C18)	(C19)

Signature of tenderer from Annex B _____

Date: _____

(C20) Total tender value	(C21) Total Exempt Imported content	(C22) Total Tender value net of exempt Imported content	(C23) Total Imported content
(C24) Total local content	(C25) Average local content % of tender		

Annex D

Imported Content Declaration - Supporting Schedule to Annex C

(D1) Tender No.
 (D2) Tender description:
 (D3) Designated Products:
 (D4) Tender Authority:
 (D5) Tendering Entity name:
 (D6) Tender Exchange Rate: Pula

NOTE: VAT to be excluded from all calculations

EU R 9.00 GBP R 12.00

A. Exempted imported content

Calculation of imported content										Summary	
Tender item no's	Description of imported content	Local supplier	Overseas Supplier	Foreign currency value as per Commercial Invoice	Tender Exchange Rate	Local value of Imports	Freight costs to port of entry	All locally incurred landing costs & duties	Total landed cost excl VAT	Tender Qty	Exempted val
(D7)	(D8)	(D9)	(D10)	(D11)	(D12)	(D13)	(D14)	(D15)	(D16)	(D17)	(D18)
(D19) Total exempt imported value											

This total must correspond to Annex C - C.21

B. Imported directly by the Tenderer

Calculation of imported content										Summary	
Tender item no's	Description of imported content	Unit of measure	Overseas Supplier	Foreign currency value as per Commercial Invoice	Tender Rate of Exchange	Local value of Imports	Freight costs to port of entry	All locally incurred landing costs & duties	Total landed cost excl VAT	Tender Qty	Total Import
(D20)	(D21)	(D22)	(D23)	(D24)	(D25)	(D26)	(D27)	(D28)	(D29)	(D30)	(D31)
(D32) Total imported value by tenderer											

(D32) Total imported value by tenderer

C. Imported by a 3rd party and supplied to the Tenderer

Calculation of imported content										Summary	
Description of imported content	Unit of measure	Local supplier	Overseas Supplier	Foreign currency value as per Commercial Invoice	Tender Rate of Exchange	Local value of Imports	Freight costs to port of entry	All locally incurred landing costs & duties	Total landed cost excl VAT	Quantity Imported	Total Imports
(D33)	(D34)	(D35)	(D36)	(D37)	(D38)	(D39)	(D40)	(D41)	(D42)	(D43)	(D44)
(D45) Total imported value by 3rd party											

(D45) Total imported value by 3rd party

D. Other foreign currency payments

Calculation of foreign currency payments					Summary	
Type of payment	Local supplier making the payment	Overseas beneficiary	Foreign currency value paid	Tender Rate of Exchange	Local value payments	(D51)
(D46)	(D47)	(D48)	(D49)	(D50)		
(D52) Total of foreign currency payments declared by tenderer and/or 3rd party						

(D52) Total of foreign currency payments declared by tenderer and/or 3rd party

Signature of tenderer from Annex B

(D53) Total of imported content & foreign currency payments - (D32), (D45) & (D52) above

Date:

This total must correspond to Annex C - C.23

Annex E

Local Content Declaration - Supporting Schedule to Annex C

(E1) Tender No.	
(E2) Tender description:	
(E3) Designated products:	
(E4) Tender Authority:	
(E5) Tendering Entity name:	

Note: VAT to be excluded from all calculations

Local Products (Goods, Services and Works)	Description of Items purchased	Local suppliers	Value
	(E6)	(E7)	(E8)
	(E9) Total local products (Goods, Services and Works)		

(E10) Manpower costs (Tenderer's manpower cost)	
(E11) Factory overheads (Rental, depreciation & amortisation, utility costs, consumables etc.)	
(E12) Administration overheads and mark-up (Marketing, insurance, financing, interest etc.)	
(E13) Total local content	

This total must correspond with Annex C - C24

Signature of tenderer from Annex B

Date: _____